SHOWER & LOCKER

VENT
AC
SKYLIGHTS
FAN
EXIST. RAIN GUTTER TO REMAIN
HEATER VENT
STORAGE
TURF
ACCESS TO ROOF
CONC. WALK
ITEM C
ROOF "C"
SPLASH BLK.
SCUPPER
SLOPE
GYMNASIUM
BASE BID ROOF
SKYLIGHT
ITEM A
ROOF "A"
PVC CONDENSATE LINE
ELEC. CONDUIT
GUTTERS TO REMAIN
NEW WALK PADS TYP.
ITEM B
ROOF "B"
RE-USE EXIST. RIGLET (TYP.)

LEGEND

- AREA TO BE REROOFED - BASE BID ROOF W/ ASPHALT SHINGLE OVER EXIST.
- ADDITIVE BID SCHEDULE - ITEM A - ROOF "A" AREA TO BE RE-ROOFED W/ MEMBRANE ROOF OVER EXIST.
- ADDITIVE BID SCEDULE - ITEM B - ROOF "B" AREA TO BE RE-ROOFED W/ MEMBRANE ROOF OVER EXIST.
- ADDITIVE BID SCHEDULE - ITEM C - ROOF "C" AREA TO BE RE-ROOFED W/ MEMBRANE ROOF OVER EXIST.

SCALE: 1/8"=1'-0"

DOUGLASS AVE
UNIVERSITY AVE.
KANSAS AVE.
POOL
MAIN BLDG.
WORK LIMIT LINE
SHOWER & LOCKER
ALTERNATE ACCESS W/ HOURS RESTRICTED TO: M-F BEFORE 7AM SAT. & SUN. ALL DAY
GYM BASE BID ROOF
GYM ROOF TO RECEIVE NEW ROOF OVER EXIST.
CHILDRENS PLAY AREA
PARKING LOT
ALLOWABLE VEHICULAR ACCESS TO ROOF.

SITE ACCESS PLAN

NTS

BOBBY BONDS REROOF

city of riverside
park & recreation
department
(714) 782-5223
3900 MAIN ST RIVERSIDE, CALIFORNIA 92522

revisions	by

date	8-26-91
design	JH
drawn	JH
check	
acc't. no.	P-0021
SHEET	1 of 1

PLAN NO. 0021