SHADING STANDARD

PLAN

PROPOSED CONSTRUCTION

PCC

AC PAVING
(BEHIND CURB)
DICK 1648 *

AC PAVING
(ROADWAY)

AC OVERLAY
SPEED-O-PRINT 952 *

DG SURFACE
DICK 1636 *

REMOVE & REPLACE 2
DICK 1634 *

EXISTING CONSTRUCTION

PCC

AC

BUILDING
MILO HARDING 92 *

ROOF OR OVERHANG

* BRAND AND NUMBER OF SCREEN PLATE.

SECTION

PROPOSED CONSTRUCTION

PCC

AC PAVING

BASE 1

EXISTING CONSTRUCTION

PCC

AC PAVEMENT
SPEED-O-PRINT 955 * 2

ROCK

UNDISTURBED SOIL
SPEED-O-PRINT 955 * 2

FILL COMPACTIONS

95% RELATIVE COMPACTION
DICK 1627 *

90% RELATIVE COMPACTION
DICK 1629 *

85% RELATIVE COMPACTION
DICK 1633 *

APPROVED _____ DATE _____
DIRECTOR OF PUBLIC WORKS

REVISIONS

DATE	MARK	BY	
7-7-82	1	[illegible]	Removed D.G. from Base
[illegible]	2	[illegible]	Added Remove & Replace and Speed-O-Print 952.

SHADING STANDARD

CITY OF RIVERSIDE · CALIFORNIA

ENGINEERING DIVISION · DEPT. OF PUBLIC WORKS

STANDARD DRAWING NO. 3