


NO. 3 REBAR 6" C.C. AND AS SHOWN AROUND FRAME

T.C. AND F.L. ELEVATIONS TO BE GIVEN ON PLANS


22" Ø CLEAR OPENING FRAME & COVER ALHAMBRA FDY. A-1530 OR EQUAL APPROVED BY CITY.

2" END CLEARANCE (typ)


T.C. AND F.L. ELEVATIONS TO BE GIVEN ON PLANS



**TOP VIEW**




**SECTION A-A**



**DOWEL DETAIL**

TO BE USED WHEN TOP IS POURED SEPARATE, ONE AT EACH CORNER



**CHANNEL DETAIL**

APPROVED BY  
*[Signature]*  
CITY ENGINEER

5/18/11  
DATE

CITY OF RIVERSIDE  
PUBLIC WORKS DEPARTMENT

CATCH BASIN

STANDARD DRAWING NO. 405

MARK	REVISIONS	APPR.	DATE

# NOTES:

1. CONCRETE shall be 560-C-3250 Portland Cement Concrete.
2. CONNECTOR PIPE shall be horizontally centered on the wall of the catch basin which faces the connector pipe.
3. CURVATURE of the lip and sidewall at the opening shall be formed by curved forms and shall not be made by plastering.
4. DIMENSIONS:
  - W shall be as specified on the plan (4' min.).
  - V shall be as specified on the plan.
  - D = 3' unless otherwise specified on the plan.
  - t = 6" if V is 4' or less.
  - t = 8" if V is between 4' and 8'.
  - t = 10" if V is 8' or more.
  - Thickness of the wall under the opening shall be t + 2" when W exceeds 7'-0".
  - t > 6", widening of wall shall be on street side.
5. CHANNEL shall be constructed in catch basins having inlet pipes. Where V minus shelf height is less than 2-1/2' the channel may be omitted.
6. STEP SPACING
  - If V is 3.5' or less, no steps are required.
  - If V is more than 3.5' and not more than 4', install one step 12" above the floor.
  - If V is more than 4', install steps 12" apart with the top step 20" to 24" below the top surface of the basin.
  - When the basin has a channel use V minus shelf height to determine step spacing.
7. PIPES shall be trimmed to the final shape and length before concrete is poured.
8. SURFACE of all exposed concrete in basin shall conform in slope, grade, color, finish and scoring to the existing or proposed curb and walk adjacent to the basin and shall be free from protruding wires and nails. Floor of channel shall be given a steel-troweled finish.
9. TOP OF BASIN shall slope 2% toward curb except when otherwise shown on the plan or to fit existing sidewalk. To be poured monolithic with S/W if curb S/W is used.
10. FRAME AND COVER shall be located as shown on sheet 1 unless otherwise shown on the plan.

APPROVED BY  
  
 CITY ENGINEER

5/18/11  
 DATE

CITY OF RIVERSIDE  
 PUBLIC WORKS DEPARTMENT

CATCH BASIN

STANDARD DRAWING NO. 405

MARK	REVISIONS	APPR.	DATE