Ac. - Acre
Ang. or ∠ - Angle
Area - Spell Out
Ave. - Avenue
Avg. - Average
Blvd. - Boulevard
Calc. - Calculated
C - Center
Cir. - Circle
c.f.m. - Cubic Feet/Minute
c.f.s. - Cubic Feet/Second
corr. - Corrugated
Co. - County or Company
C.M.P.- Corrugated Metal Pipe
C.M.P.A. - Corrugated Metal Pipe Arch
cor. - Corner
C.P. Concrete Pipe
C.R. - Curb Return
cu. ft. - Cubic Feet
c.y. - Cubic Yards
D.G. - Decomposed granite
Dr. - Drive
E - East
E'ly - Easterly
Elev.- Elevation
Est. - Estimate
E.T.W. - Edge of Traveled Way
Ft - Foot
F.B. - Field Book
Fd. - found
Gar. - Garage
guy - Guy wire or pole
Hse. - House
Irr. - Irrigation Pipe
Lat. - Latereal
L.F. - Linear Feet
Ln. - Lane
Lt - Left
Min. - Minimum
M.O. - Middle Ordinate
M.O.C. - Middle of Curve

N - North
N'ly - Northerly
NE'ly - Northeasterly
NW'ly - Northwesterly
N.I.C. - Not In Contract
N.T.S. - Not to Scale
No. - Number
Pl. - Place
Pt. - Point
R - Radius
R & R - Remove and Replace
Rd. - Road
R.E. - Registered Engineer
Rec. - Record
Riv. - Riverside
R/S - Record of Survey
Rwy. Railway
Rt. - Right
R.W. Hdr. - Redwood Header
S.B. - San Bernardino
SBB&M - San Bernardino Base and Meridian
S - South
S'ly - Southerly
SE'ly - Southeasterly
SW'ly - Southwesterly
Sec. - Section
Shld. Shoulder
Sq. - Square
Spk. - Spike
St. - Street
Stk. - Stake
T.P. - Top of Pavement
Typ. - Typical
Vic. - Vicinity
V.P.I. - Vertical Point of Intersection
W - West
W'ly - Westerly

APPROVED BY
CITY ENGINEER — DATE 5/18/11

MARK	REVISIONS	APPR.	DATE

CITY OF RIVERSIDE
PUBLIC WORKS DEPARTMENT

STANDARD ABBREVIATIONS

STANDARD DRAWING NO. 2

Sheet 1 of 1