



BILL OF MATERIALS		
	QUANTITY	REF
① CML&C STEEL OR DIP WATER MAIN	PER PLAN	
② 1" THREADED OUTLET	1	CWD-340
③ 1" BALL CORP STOP (MIPT x MIPT)	2	
④ 1" GALV STEEL COUPLING	2	
⑤ 1" PVC ADAPTER	2	
⑥ 1" PVC PIPE	VARIES	
⑦ 1" BRASS CAP	1	
⑧ 10" GATE BOX AND SPLIT-SLEEVE	1	CWD-515

NOTES:

- 1.) CONTRACTOR SHALL REMOVE VALVE BOX, CLOSE AND CAP 1" BALL CORP STOP AND REMOVE PVC RISER FOLLOWING ACCEPTANCE OF THE TRANSMISSION MAIN.
 - 2.) STATION, LOCATION, AND SPECIAL NOTES PER PLAN AND PROFILE SHEETS.
- Ⓐ DOUBLE-STRAP SERVICE SADDLES SHALL BE USED ON ALL DIP CONNECTIONS



WATER DISTRIBUTION & TRANSMISSION
PIPELINE CONSTRUCTION METHODS

TEMPORARY
WATER SAMPLER