

*City of Riverside***Underground Construction Standards**
UGS-008

4-1-68

DUCT BANK & DUCT TERMINAL REQUIREMENTS

Each duct installation shall be in conformance with the requirements set forth
In the drawings, specifications, schedules and tabulations referred to below:

1. Concrete in accordance with UGS-015.
2. Concrete envelope complete or partial - concrete cap cover- direct burial duct in accordance with UGS-125, UGS-125.2 and/or UGS-125.3.
3. Duct material in accordance with UGS-100
4. Duct entrance to underground structures to be in accordance with UGS-100.1, 110, 110.1, 110.2, & 110.4.
5. Trench terminals in accordance with UGS-112 for ducts terminated in main trench.
6. Service lateral terminals in accordance with UGS-113.
7. Riser end of riser ducts in accordance with UGS-115, UGS-116, OR UGS-117.
8. Duct alignment in accordance with UGS-100 and UGS-100.1